

- ADA & TAS Compliant (lower or "concave" stations only)
- Patented Molded One-Piece Design with Integral Bowls
- Constructed of Terreon® or Terreon®RE Solid Surface Material
- Trap and Transition Cover Enclosure
- Includes Capacitive Sensing Faucet
- Optional Electric Tankless Water Heater, Soap Dispenser and Plug-in Transformer

## Specifications

With its patented design, the multi-height Frequency Lavatory System comfortably provides hand-washing access for adults, children, and those with disabilities. The "convex" or higher station provides a more ergonomically correct position for able-bodied users while the "concave" or lower stations can be mounted to meet ADA or TAS guidelines. Accommodating one to two users at a time, the FL-Series features a solid surface countertop with a one-of-a-kind integral bowl. The unique bowl, with integral solid surface overflow allows for greater knee clearance than other barrier free fixtures. The Frequency Lav System includes a "no-drip" edge and comes equipped with centershank battery-operated, capacitive sensing faucets. Faucet includes an anti-rotation 4" trim plate. Optional deck-mounted soap dispensers, plug-in transformers and electric tankless water heaters are available.

## Construction

### Counter Top/Bowl


Constructed of Terreon, a densified solid surface material composed of polyester resin, or TerreonRE, a densified solid surface material composed of a bio-based resin and preconsumer recycled granules. Terreon and TerreonRE are resistant to chemicals, stains, burns and impact. Surface damage can be easily repaired with everyday cleansers or fine grit abrasives. Terreon and TerreonRE are certified by NAHB to meet ANSI Z124.3, Z124.6 and ANSI/ICPA SS-1. Terreon and TerreonRE are GREENGUARD® certified as low-emitting materials.

### Trap Cover Enclosure

The trap and transition cover of the Frequency Lav System not only conceals plumbing and electrical connections, but also reduces time needed for installation and maintenance. Trap and transition cover are made from Class A fire-rated polystyrene, available in three colors.

### Mounting

The FL-Series includes heavy gauge stainless steel mounting brackets, eliminating the need for additional specifications and/or casework beneath the countertop. All Frequency Lavatory Systems meet or exceed industry standards for load testing.



## Code Compliance and Certifications

### ANSI Standards

Terreon and TerreonRE are certified by NAHB to meet ANSI Z124.3, Z124.6 and ANSI/ICPA SS-1.

### cUPC Approval

Frequency Lav Systems are Uniform Plumbing Code (UPC), International Plumbing Code (IPC) and National Plumbing Code of Canada (NPC) approved through the International Association of Plumbing and Mechanical Officials (IAPMO). Manufactured in compliance with IGC 156, CSA B45 Series (R08) & ASME A112.18.1/CSA B125.1.

- This plumbing fixture is designed for hand washing only. It is not Intended to dispense water for human consumption through drinking or for preparation of food or beverages.

### Standard Height Mounting

The concave or lower hand washing stations are designed to be mounted at various heights to comply with all ADA guidelines on reaches and clearances. To comply with ADA, the rim height at the outside edge of the lower or concave station must be 34" max. above the finished floor. To be completely ADA compliant, the Frequency Lav System must be equipped with ADA-compliant faucets and trap cover enclosure.

- The convex hand washing stations do not meet ADA Accessibility Guidelines. Always check local codes for compliance.

### Juvenile Height Mounting

The concave hand washing stations are designed to be mounted at various heights to comply with all ADA and TAS guidelines on reaches and clearances. To comply with ADA for children, the rim height at the outside edge of the concave station must not exceed 31". Source: ADA Accessibility Guidelines for Buildings and Facilities (ADAAG) as amended through September 2002.

To comply with Texas Accessibility Standards for children, the concave (lower) hand washing stations must be mounted so the rim height at the outside edge does not exceed 30" or 32" based on age or grade level. For more information, contact the Texas Department of Licensing and Regulation.



Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

## Standard Equipment

### Models FL-2H & FL-2L

Multi-level deck with two lavatories, heavy gauge, stainless steel mounting brackets and two battery-operated faucets described below. Trap and transition covers to enclose the following fittings: offset drain; P-trap; continuous waste with end outlet; flexible stainless steel supply connections; and ASSE 1070 Navigator® thermostatic mixing valve with stop valves.

## Activation Controls

### Capacitive Sensing Technology

The Aerada 1200 Series CS faucet creates an omnidirectional detection zone utilizing capacitive sensing technology. The capacitive sensing field triggers faucet activation only when a significant change in the capacitive field occurs. Only human presence will create a significant change in the capacitive field. As such, inanimate objects will not trigger faucet activation. The faucet is unaffected by varying skin tones, other infrared presence and soap scum build-up.

### Valve

The electronically activated motor driven valve provides reliable performance since there are few moving parts. The valve includes an in-line filter to trap debris and is unaffected by most chemicals and minerals found in municipal water supplies. Valve features a factory-set maximum water run-on duration of 15 seconds. Valve control module features a manual override control for applications requiring periodic flushing of the water lines. The valve and electronics are enclosed in a water-resistant housing mounted below the fixture.

### Flow Control/Rate

Operating water pressure range is 20–80 psi. Flow regulator keeps flow rate constant at all pressures. The flow is laminar at a rate of .5 gpm.

## Optional Equipment

### Models FL-2H & FL-2L


Liquid soap dispenser, 100–120 VAC plug-in transformer (to convert battery operated faucets) and electric tankless water heater (described below).

### Thermostatic Electric Tankless Water Heater

The electric tankless water heater is equipped with a micro processing temperature control capable of maintaining outlet temperature accuracy of +/- 1°F. Flow switch activates heater only on demand with 99% efficiency. For easy service, the heater features a replacement cartridge element.

Model	KW	VAC	Amps	Temp. Rise @1GM
EX95TMLB	9.5	240/208*	40	65° F
EX100TMLB	10	277	36	68° F

\*240 volt can also be rated 208 volts with a 25% reduction in power




Verify all rough-in dimensions prior to installation.


Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Protected by one or more of the following U.S. patents: D477,060, D507,634, D527,809, D537,927, and 7,039,963. Other patents pending.


**Dimensions – Top and Front Views**







**FL-2H**




**FL-2L**



**Dimensions – Side Views**




## Rough-Ins for FL-2H



Code	Description	Qty.
A	3/8" Lav Deck Anchors with a Minimum Pull-Out Force of 1,000 lbs.	6
B	#10 Wall Anchors/Fasteners for Mounting Trap/Transition Covers	5
H, C	1/2" Nominal Copper Tubing Hot/Cold Supplies, Stub-Out 2" From Wall	1
D	#10 Wall Anchors/Fasteners for Valve Mounting	2
E	110v GFI Protected Electrical Outlet	1
W	1 1/2" NPT Drain, stub out 2" from wall (for <b>combined</b> drain) <b>NOTE: For individual drains, refer to page 9.</b>	1

Rim Height	Vertical Height Adjustments for codes A–E, H, C and W	Fixture Style
34"	0	Standard Height
32"	Subtract 2"	TAS, Grades 6 through 8 or 9
31"	Subtract 3"	TAS, Pre-K through Grades 5 or 6
30"	Subtract 4"	Juvenile Height

## Rough-Ins for FL-2L



Code	Description	Qty.
A	3/8" Lav Deck Anchors with a Minimum Pull-Out Force of 1,000 lbs.	6
B	#10 Wall Anchors/Fasteners for Mounting Trap/Transition Covers	5
H, C	1/2" Nominal Copper Tubing Hot/Cold Supplies, Stub-Out 2" From Wall	1
D	#10 Wall Anchors/Fasteners for Valve Mounting	2
E	110v GFI Protected Electrical Outlet	1
W	1 1/2" NPT Drain, stub out 2" from wall (for <b>combined</b> drain) <b>NOTE: For individual drains, refer to page 9.</b>	1

Rim Height	Vertical Height Adjustments for codes A–E, H, C and W	Fixture Style
34"	0	Standard Height
32"	Subtract 2"	TAS, Grades 6 through 8 or 9
31"	Subtract 3"	TAS, Pre-K through Grades 5 or 6
30"	Subtract 4"	Juvenile Height

Model	Description
<input type="checkbox"/> FL-2H	Frequency Lavatory System, Double Station (high on left), includes battery-operated S53-315 faucets
<input type="checkbox"/> FL-2L	Frequency Lavatory System, Double Station (low on left), includes battery-operated S53-315 faucets

### Standard Selections (Must select one from each category)

#### Supply (select one):

- |                                      |  |
|--------------------------------------|--|
| <input type="checkbox"/> TMA         | Navigator Thermostatic Mixing Assembly (Hot & Cold Supplies) |
| <input type="checkbox"/> TL          | Single Tempered Line   |
| <input type="checkbox"/> HEAT277     | Electric Tankless Water Heater, 277 Volts                    |
| <input type="checkbox"/> HEAT240-208 | Electric Tankless Water Heater, 240/208 Volts                |

#### Soap Dispenser (select one):

- |                              |                       |                              |                   |
|------------------------------|-----------------------|------------------------------|-------------------|
| <input type="checkbox"/> LSD | Liquid Soap Dispenser | <input type="checkbox"/> NSD | No Soap Dispenser |
|------------------------------|-----------------------|------------------------------|-------------------|

#### Color of Terreon® Bowl/Deck(select one):

##### Standard Colors

- |                                  |                |                                   |               |
|----------------------------------|----------------|-----------------------------------|---------------|
| <input type="checkbox"/> E-GRAY  | Empire Gray    | <input type="checkbox"/> GRAPH    | Graphite      |
| <input type="checkbox"/> BONE    | Mesa Bone      | <input type="checkbox"/> LANNON   | Lannonstone   |
| <input type="checkbox"/> PEP-WHT | Peppered White | <input type="checkbox"/> COBBLE   | Cobblestone   |
| <input type="checkbox"/> SAND    | Sandtrap       | <input type="checkbox"/> WHT-SAND | White Sand    |
| <input type="checkbox"/> DS-WHT  | Designer White | <input type="checkbox"/> FIESTA   | Fiesta        |
| <input type="checkbox"/> CHAR    | Charcoal Gray  | <input type="checkbox"/> LONDON   | London Gray   |
| <input type="checkbox"/> JADE    | Jade           | <input type="checkbox"/> O-TAUPE  | Organic Taupe |

##### Designer Colors\* (available at an additional charge)

- |                                   |             |                                   |              |
|-----------------------------------|-------------|-----------------------------------|--------------|
| <input type="checkbox"/> ARC-CHIP | Arctic Chip | <input type="checkbox"/> COFFEE   | Coffee Bean  |
| <input type="checkbox"/> S-SAGE   | Summer Sage | <input type="checkbox"/> CORN     | Cornfield    |
| <input type="checkbox"/> RIVER    | Riverstone  | <input type="checkbox"/> BLUESKY  | Blue Sky     |
| <input type="checkbox"/> MYSTIC-M | Mystic Moss | <input type="checkbox"/> HILLSIDE | Hill Side    |
| <input type="checkbox"/> STAR-D   | Stardust    | <input type="checkbox"/> MOUNTAIN | Mountain Top |

##### TerreonRE Colors (available at an additional charge)

- |                                     |            |                                   |           |                                     |            |
|-------------------------------------|------------|-----------------------------------|-----------|-------------------------------------|------------|
| <input type="checkbox"/> BIRCH-BARK | Birch Bark | <input type="checkbox"/> MAIZE    | Maize     | <input type="checkbox"/> OCEAN-MIST | Ocean Mist |
| <input type="checkbox"/> DUSK       | Dusk       | <input type="checkbox"/> MOONDUST | Moon Dust | <input type="checkbox"/> OLIVE      | Olive      |
| <input type="checkbox"/> FERN       | Fern       | <input type="checkbox"/> OAT      | Oat       |                                     |            |

##### Element Colors

- |                                  |                |                                 |            |
|----------------------------------|----------------|---------------------------------|------------|
| <input type="checkbox"/> SS-GRAY | Soapstone Gray | <input type="checkbox"/> CA-TAN | Canyon Tan |
|----------------------------------|----------------|---------------------------------|------------|

#### Color of Trap Cover (select one):

- |                               |      |                                |       |
|-------------------------------|------|--------------------------------|-------|
| <input type="checkbox"/> GRAY | Gray | <input type="checkbox"/> PUTTY | Putty |
| <input type="checkbox"/> COAL | Coal |                                |       |

### Optional Selections

#### Transformer:

- |                             |   |
|-----------------------------|---|
| <input type="checkbox"/> PT | 110-120VAC plug-in adapter to convert battery-operated S53-315 faucet |
|-----------------------------|---|

\* Non-cancelable, non-returnable.

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.